

Distributed by:



www.Jameco.com ♦ 1-800-831-4242

The content and copyrights of the attached
material are the property of its owner.

Quality Engineering Test Report

SERIES: SP-300 300W AC-DC SINGLE OUTPUT SWITCHING POWER SUPPLY

SAMPLE: A.SP-300-5 5V / 50A D.SP-300-13.5 13.5V / 21A G.SP-300-27 27V / 11A
 B.SP-300-7.5 7.5V / 34A E.SP-300-15 15V / 19A H.SP-300-48 48V / 6.25A
 C.SP-300-12 12V / 24A F.SP-300-24 24V / 12.5A

NO	TEST ITEM	TEST CONDITION / SPECIFICATION	RESULT	VERDICT
1	AC INPUT VOLTAGE RANGE	I/P:TESTING SPEC:88~264VAC O/P:FULL LOAD	A:52.4VAC~267VAC	P
2	LINE REGULATION	I/P:88~264VAC SPEC: O/P:FULL LOAD A: $\pm 0.5\%$ B: $\pm 0.5\%$ C: $\pm 0.3\%$ D: $\pm 0.3\%$ E: $\pm 0.3\%$ F: $\pm 0.3\%$ G: $\pm 0.2\%$ H: $\pm 0.2\%$ $\pm 0.2\%$	A: -0.118% ~ 0% B: 0% ~ 0% C: 0.05% ~ 0.05% D: -0.04% ~ -0.04% E: 0% ~ 0% F: -0.02% ~ 0% G: +0% ~ +0% H: 0% ~ 0%	P
3	LOAD REGULATION	I/P:230VAC SPEC: O/P:MIN. TO FULL LOAD A: $\pm 1\%$ B: $\pm 1\%$ C: $\pm 0.5\%$ D: $\pm 0.5\%$ E: $\pm 0.5\%$ F: $\pm 0.5\%$ G: $\pm 0.5\%$ H: $\pm 0.5\%$ $\pm 0.5\%$	A: -0.118% ~ +0% B: -0.33% ~ +0.24% C: -0.1% ~ +0.15% D: -0.09% ~ +0.09% E: -0.04% ~ +0.04% F: -0.07% ~ +0.05% G: -0.06% ~ +0.1% H: -0.09% ~ +0.16%	P
4	OUTPUT VOLTAGE TOLERANCE	I/P:88~264VAC SPEC: O/P:0% TO FULL LOAD A: $\pm 2\%$ B: $\pm 2\%$ C: $\pm 1\%$ D: $\pm 1\%$ E: $\pm 1\%$ F: $\pm 1\%$ G: $\pm 1\%$ H: $\pm 1\%$ $\pm 1\%$	A: -0% ~ +0.118% B: -0.66% ~ 0% C: -0.26% ~ +0% D: -0.19% ~ +0.05% E: -0.05% ~ -0.16% F: -0.15% ~ -0.03% G: -0.2% ~ +0.1% H: -0.22% ~ +0.04%	P
5	RIPPLE&NOISE	I/P:230VAC SPEC: O/P:FULL LOAD A: 150mV B: 150mV C: 150mV D: 150mV E: 150mV F: 150mV G: 200mV H: 240mV	A: 87mV B: 117mV C: 69mV D: 57mV E: 87mV F: 70mV G: 60mV H: 55mV	P
6	AC INPUT CURRENT	I/P:230VAC SPEC:2A O/P:FULL LOAD	G :1.516A	P
7	MAX. INRUSH CURREN	I/P:230VAC SPEC:36A O/P: FULL LOAD	G :27.296A	P
8	O/P VOLTAGE ADJ.RANGE	I/P:230VAC SPEC: A: 4.5~5.7V O/P:MIN. LOAD B: 6~9V C: 10~13.2V D: 12~15V E: 13.5~18V F: 20~26.4V G: 26~32V H: 41~56V	A: 4.35V~6.21V B: 5.58V~9.68V C: 9.276V~13.824V D: 11.41V~16.29V E: 12.43V~18.88V F: 17.9V~27.55V G: 24.75V~35.92V H: 39.69V~58.20V	P
9	SET UP TIME	I/P:230VAC SPEC:1500mS O/P:FULL LOAD	G: 745.1mS	P
10	HOLD UP TIME	I/P:230VAC SPEC:20mS O/P:FULL LOAD	G: 45.85mS	P
11	EFFICIENCY	I/P:230VAC SPEC: A:75% O/P:FULL LOAD B:80% C:83% D:83% E:83% F:85% G:86% H:85%	A:77.86% B:81.06% C:84.16% D:85.13% E:83.81% F:86.57% G:86.18% H:87.87%	P

NO	TEST ITEM	TEST CONDITION / SPECIFICATION	RESULT	VERDICT																																								
12	OVER LOAD PROTECTION	I/P:230VAC SPEC: 105%~135% O/P:TESTING	A:116.7% B:120% C:120% D:132.4% E:116.5% F:123.4% G:116% H:118.77%	P																																								
13	OVER VOLTAGE PROTECTION	I/P:230VAC SPEC: A:5.75V~6.75V O/P:TESTING B:9.4V~10.9V C:13.8V~16.2V D:15.5V~18.2V E:18V~21V F:27.6V~32.4V G:33.7V~39.2V H:57.6V~67.2V	A:6.42V B:9.59V C:14.4V D:17.45V E:19.84V F:28.78V G:37.8V H:58.21V	P																																								
14	OVER TEMPERATURE PROTECTION & FAN ON/OFF TEST	I/P:230VAC SPEC: RTH1 or RTH2 O/P:FULL LOAD OTP >= 70°C FAN ON >= 50°C FAN OFF <= 45°C	A: OTP : 76.5°C FAN ON : 57°C FAN OFF: 48°C	P																																								
15	POWER FACTOR	I/P:230VAC SPEC: 0.95 O/P:FULL LOAD	A: 0.989	P																																								
16	GROUND LEAKAGE CURRENT	I/P:240VAC SPEC: L-FG-<1mA N-FG-<1mA	A: L-FG:0.77mA N-FG:0.76mA	P																																								
17	INSULATION RESISTANCE	SPEC: I/P-O/P: 500VDC/100M Ohms MIN. I/P-FG: 500VDC/100M Ohms MIN. O/P-FG: 500VDC/100M Ohms MIN.	A: O/P-FG >100M Ohms I/P-O/P >100M Ohms I/P-FG >100M Ohms	P																																								
18	DIELECTRIC / WITHSTAND VOLTAGE	SPEC: I/P- O/P: 3KVAC/ 1 min. (10mA CUT-OFF) I/P - FG: 1.5KVAC/ 1 min. (10mA CUT-OFF) O/P -FG: 0.5KVAC/ 1 min. (10mA CUT-OFF)	G: I/P-O/P :0.002mA I/P-FG :3.74mA O/P-FG :6.81mA	P																																								
19	BURN-IN TEST	I/P: 230VAC O/P: FULL LOAD TA:30.4°C BURN-IN DURATION : 1.5 hrs	A:NON BREAK	P																																								
20	ENVIRONMENT TEST	HIGH AMBIENT TEMPERATURE FULL LOAD TEST I/P:230VAC O/P:FULL LOAD AMBIENT TEMPERATURE:36.7 °C	A: AFTER 14 hrs NON BREAK	P																																								
21	TEMPERATURE RISE TEST T _{rise} OF PARTS	A: I/P :230VAC AFTER 1.5 hr BURN-IN O/P :FULL LOAD TA:30.4 °C <table><tr><th>POSITION</th><th>P/N</th><th>TEMP</th><th>T_{rise}</th></tr><tr><td>BD1</td><td>BRIDGE DIODE</td><td>47.0°C</td><td>16.6°C</td></tr><tr><td>Q6</td><td>MAIN TRANSISTOR</td><td>51.9°C</td><td>21.5°C</td></tr><tr><td>T1</td><td>MAIN TRANSFORMER WIRE</td><td>59.4°C</td><td>29°C</td></tr><tr><td>D11</td><td>O/P DIODE</td><td>80.1.°C</td><td>49.7°C</td></tr><tr><td>C33</td><td>O/P FILTER CAPACITOR</td><td>53.5°C</td><td>23.1°C</td></tr><tr><td>L1</td><td>O/P CHOCK</td><td>70.5°C</td><td>40.1°C</td></tr><tr><td>RTH1</td><td>SURGE DIODE</td><td>55.5°C</td><td>25.1°C</td></tr><tr><td>RTH2</td><td>SURGE DIODE</td><td>46.1°C</td><td>15.7°C</td></tr><tr><td>L3</td><td>O/P CHOCK</td><td>50.6°C</td><td>20.2°C</td></tr></table>		POSITION	P/N	TEMP	T _{rise}	BD1	BRIDGE DIODE	47.0°C	16.6°C	Q6	MAIN TRANSISTOR	51.9°C	21.5°C	T1	MAIN TRANSFORMER WIRE	59.4°C	29°C	D11	O/P DIODE	80.1.°C	49.7°C	C33	O/P FILTER CAPACITOR	53.5°C	23.1°C	L1	O/P CHOCK	70.5°C	40.1°C	RTH1	SURGE DIODE	55.5°C	25.1°C	RTH2	SURGE DIODE	46.1°C	15.7°C	L3	O/P CHOCK	50.6°C	20.2°C	P
POSITION	P/N	TEMP	T _{rise}																																									
BD1	BRIDGE DIODE	47.0°C	16.6°C																																									
Q6	MAIN TRANSISTOR	51.9°C	21.5°C																																									
T1	MAIN TRANSFORMER WIRE	59.4°C	29°C																																									
D11	O/P DIODE	80.1.°C	49.7°C																																									
C33	O/P FILTER CAPACITOR	53.5°C	23.1°C																																									
L1	O/P CHOCK	70.5°C	40.1°C																																									
RTH1	SURGE DIODE	55.5°C	25.1°C																																									
RTH2	SURGE DIODE	46.1°C	15.7°C																																									
L3	O/P CHOCK	50.6°C	20.2°C																																									
22	LIFE CYCLE	A: SUPPOSE C33 IS THE MOST CRITICAL COMPONENT I/P:230VAC O/P:FULL LOAD Ta:25°C Tc33:48.1°C Life: 339518hrs I/P:230VAC O/P:FULL LOAD Ta:45°C Tc33:55.9°C Life: 197674hrs		P																																								
23	CRITICAL COMPONENT RECORD (FOR QC INSPECTION REFERENCE ONLY)	A: FUSE :6.3AL/250V BRIDGE DIODE :D10XB60 LINE FILTER :TF360 ET-28 TRANSFOMER :TF362-R1 ETD-39 POWER SWITCHER :2SK2652 TO-3P OUTPUT DIODE :ESAE83-004 60A/40V OUTPUT CAPACITOR :RUBYCON 3300uF/10V 105 °C YXG INPUT CAPACITOR :HITACHI 150uF/400V 85°C HP3 P.C.B :SP-300N-R5 FR-4 2 OZ DS																																										

[PREVIOUS](#)
[NEXT](#)

DATE	SAMPLE	TEST RESULT	TEST	APPROVAL
980519	SP-300	PASS	H.C.LIOU	Max Lin
20010420	PRODUCT DA13021298 SP-300-5,7.5	PASS	VINCENT	Max Lin
20010515	PRODUCT CA14053897 SP-300-7.5	PASS	VINCENT	Max Lin
20010531	PRODUCT A104B02A SP-300-5,12	PASS	VINCENT	Max Lin
20020605	PRODUCT A2005B26D 27V	PASS	VINCENT	Max Lin

[PREVIOUS](#)